EXTRA ITEM RATE LIST

Name of Work: Providing and fixing Street Sign boards in Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.

Name of Agency: Sri N.N. Srinivasaiah, # 2405, Sahakaranagara E Block, Bangalore - 560 092.

Estimated Cost: Rs. 40,00,000.00

Tender Amount : Rs. Rs. 30,13,699.14

Work Order No. BBMP/EE/BTP/WO/103/2020-21 Dated: 09.09.2020.

Sl. No.	Item No.	Description of Work	Unit	Qty	Rate	Amount	Whether the items are alternative to items in tender schedule or whether being an additional item	Wheather the extra items s included in the sanctioned Estimate	How the expenditure due to the extra item is proposed to be met out	Whether the item isincluded in the S.R (Referabce if SR to be given . If not Data Should accompany the EIRL	Remarks
1	E1	Supply and fixing of **Retro Reflective Single Arrow Road Name Signboard of size 1600 mm x 900 mm made** out of retro reflective sheeting conforming to Type XI standrads of ASTM D 4956 - 09 & as per IRC 67-2012 for full back ground of dlue colour and white letters and fixed over 4 mm thick aluminium composite materials sheet having minimum 0.5 mm thick aluminium skin on both sides with back side painted grey colour and fixed over back supportframe SS angle of 15 mm x 20 mm x 1.2 mm supported by 38 mm OD stainless steel pipe all round in 304 grade and 2 nos of vertical posts of 50 mm OD stainless steel pipe of 202 grade firmly fixed to the ground means of properly designed foundation of size 450 mm x 450 mm x 600 mm in 1:1.5:3 ratio cement concrete the background shall be blue in color	Sqm	37.20	11896.03	442532.32	Additional Item	No	By over all savings in the work	2018-19 PWD SR Rates	
		Total				**442532.32**					

Percentage Excess $\frac{\text{442532.32}}{\text{Approved Tender Amount } \text{3013699.14}} \times 100 =$ 14.68%

Assistant Engineer
Ward No. 11

"EIRL APPROVED"

Assistant Executive Engineer
Vidyaranyapura Sub Division
BBMP, Bangalore - 97

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92